GENERAL NOTES & RESTRICTIONS

1. A GEOTECHNICAL INVESTIGATION WAS PERFORMED BY A.G.E.C., INC. THE INVESTIGATION RESULTS AND SPECIFIC RECOMMENDATIONS FOR THE CONSTRUCTION OF FOUNDATIONS, FLOOR SLABS AND EXTERIOR FLATWORK ARE COMPILED IN A REPORT DATED APRIL 24, 2020. THIS REPORT IS AVAILABLE FROM THE DEVELOPER AND A COPY ON FILE WITH IVINS CITY. OWNERS, BUILDERS AND CONTRACTORS SHOULD BECOME FAMILIAR WITH THIS REPORT AND COMPLY WITH ITS RECOMMENDATIONS.

2. ALL LOTS ARE SUBJECT TO A 10 FOOT WIDE PUBLIC UTILITY AND DRAINAGE EASEMENT ALONG THE FRONT AND STREET SIDE LOT LINES AND A 7.5 FOOT WIDE PUBLIC UTILITY AND DRAINAGE EASEMENT ALONG ALL INTERIOR AND REAR LOT LINES UNLESS OTHERWISE NOTED.

3. ALL LOTS IN THIS SUBDIVISION ARE SUBJECT TO A 25 FOOT BUILDING SETBACK ALONG ALL FRONT AND STREET FACING SIDES, 10 FOOT SETBACKS ON ALL INTERIOR SIDE YARDS, AND A 10 FOOT SETBACK ON REAR YARDS UNLESS OTHERWISE NOTED. SETBACKS ALONG KWAVASA DRIVE ARE 10 FOOT DUE TO THE EXISTING LANDSCAPE STRIP.

4. DIMENSIONS SHOWN TAKE PRECEDENCE OVER SCALE.

5. ALL COORDINATES LISTED ARE UTAH SOUTH ZONE NAD 83 STATE PLANE (GRID) COORDINATES.

6. ALL BEARINGS ARE DERIVED FROM THE BASIS OF BEARING SHOWN HEREON.

7. ALL DISTANCE LISTED ARE GROUND DISTANCES AND ARE TRUE REPRESENTATION OF MONUMENTS AND IMPROVEMENTS PLACED OR TO BE PLACED ON THE GROUND. (UNLESS OTHERWISE NOTED)

8. ALL APPROVED SEWER MAINS AND MANHOLES WITHIN PUBLIC STREETS ARE PUBLIC AND SHALL BE MAINTAINED BY IVINS CITY UNLESS OTHERWISE NOTED. ALL LATERALS, GRINDER PUMPS, AND LOW PRESSURE SEWER SYSTEMS ARE PRIVATE AND MAINTAINED BY THE PROPERTY OWNER OR PROPERTY OWNERS ASSOCIATION AS DEFINED BY THE PROPERTY OWNERS ASSOCIATION UNLESS OTHERWISE NOTED.

9. ALL APPROVED DRAINAGE IMPROVEMENTS LOCATED WITHIN PUBLIC STREETS AND SPECIFIED EASEMENTS ARE PUBLIC AND SHALL BE MAINTAINED BY IVINS CITY UNLESS OTHERWISE NOTED. DRAINAGE IMPROVEMENTS IN PRIVATE STREETS ARE PRIVATE AND SHALL BE MAINTAINED BY THE PROPERTY OWNERS ASSOCIATION OR ADJACENT PROPERTY OWNER AS DEFINED BY THE BYLAWS OF THE PROPERTY OWNERS ASSOCIATION. CITY WILL OWN AND MAINTAIN MAIN LINE STORM DRAINS THAT RECEIVE WATER FROM OFFSITE PUBLIC STREETS.

10. ALL APPROVED WATER AND IRRIGATION IMPROVEMENTS ARE PUBLIC AND SHALL BE MAINTAINED BY IVINS CITY UP TO AND INCLUDING THE METER AND METER BOX, UNLESS OTHERWISE NOTED. ALL FIRE HYDRANTS AND THEIR APPURTENANCES WITHIN THIS SUBDIVISION ARE PUBLIC AND SHALL ALSO BE MAINTAINED BY IVINS CITY, UNLESS OTHERWISE NOTED.


11. THE PROPERTY OWNER OR PROPERTY OWNERS ASSOCIATION (AS DEFINED BY THE BYLAWS OF THE PROPERTY OWNERS ASSOCIATION) SHALL BE RESPONSIBLE FOR REPAIRING, RESTORING, OR REPLACING PRIVATE DRIVEWAYS, PARKING AREAS, LANDSCAPING, FENCES, STRUCTURES OR OTHER PRIVATE IMPROVEMENTS CONTAINED WITHIN THIS SUBDIVISION RESULTING FROM DAMAGE OR DISRUPTION CAUSED BY IVINS CITY IN INSTALLING, MAINTAINING, REPAIRING, OR REPLACING PUBLIC WATER, IRRIGATION, SEWER, AND/OR DRAINAGE IMPROVEMENTS. IVINS CITY WILL REPAIR, RESTORE, OR REPLACE PRIVATE STREETS WITHIN STREET RIGHT-OF-WAYS TO A SERVICE LEVEL NOT TO EXCEED PUBLIC STREET STANDARDS. IMPROVEMENTS BEYOND TYPICAL PUBLIC STREET STANDARDS ARE THE RESPONSIBILITY OF THE PROPERTY OWNER OR THE PROPERTY OWNERS ASSOCIATION.


12. ALL STREETLIGHTS ON PRIVATE STREETS NOT MAINTAINED BY ROCKY MOUNTAIN POWER SHALL BE MAINTAINED AND POWER PAID BY THE PROPERTY OWNERS ASSOCIATION. ALL STREETLIGHTS ON PUBLIC ROADS NOT MAINTAINED BY ROCKY MOUNTAIN POWER SHALL BE MAINTAINED BY IVINS CITY.

13. ALL LOTS AND PROPERTY WITHIN THIS SUBDIVISION ARE SUBJECT TO THE TERMS AND CONDITIONS OF THE DEVELOPMENT AGREEMENTS BETWEEN _____ "HOMEOWNERS ASSOCIATION" AND "IVINS CITY" DATED _____ AND RECORDED _____. SAID DEVELOPMENT AGREEMENT SHALL BE RECORDED SIMULTANEOUS WITH THIS SUBDIVISION AND THE TERMS AND CONDITIONS THEREIN ARE INTENDED TO RUN WITH THE PROPERTY WITHIN THIS SUBDIVISION AND ALL OWNERS OF LOTS WITHIN THIS SUBDIVISION AND "HOMEOWNERS ASSOCIATION" OWNERS ASSOCIATION ACKNOWLEDGE AND AGREE THAT THEY HAVE READ OR HAVE THE OPPORTUNITY TO READ THE AGREEMENT AND AGREE TO BE BOUND THEREBY. (COPIES OF THE AGREEMENT MAY BE OBTAINED FROM THE IVINS CITY RECORDER OR WASHINGTON COUNTY RECORDERS OFFICE.)

14. OWNERS OF LOTS WITHIN THIS SUBDIVISION AND THE HOMEOWNERS ASSOCIATION WAIVE ANY CLAIMS AGAINST IVINS CITY FOR FLOOD OR DRAINAGE DAMAGE AS MORE PARTICULARLY DESCRIBED IN THE DEVELOPMENT AGREEMENT.

15. LANDSCAPING DESIGN, MAINTENANCE, AND CONTROL WITHIN THE PUBLIC RIGHT-OF-WAYS SHALL BE THE SOLE RESPONSIBILITY OF THE ADJOINING PROPERTY OWNER OR PROPERTY OWNERS ASSOCIATION (AS DEFINED BY THE BYLAWS OF THE PROPERTY OWNERS ASSOCIATION), ITS SUCCESSORS AND OR ASSIGNS. (UNLESS OTHERWISE NOTED) NOTE TO PREPARER OF PLAT: GENERALLY IVINS CITY WILL MAINTAIN LANDSCAPING ADJACENT TO ARTERIALS AND MAJOR COLLECTORS BUT THESE AREAS SHOULD BE NOTED ON THE PLAT.





Curve Table

Curve #	Length	Radius	Delta	Chord Direction	Chord Length
C1	26.12	150.00	9°58'43"	S85° 55' 13"W	26.09
C2	23.58	15.00	90°03'19"	N45° 52' 54"E	21.22
C3	23.55	15.00	89°56'41"	S44° 07' 06"E	21.20
C4	23.58	15.00	90°03'19"	N45° 52' 54"E	21.22
C5	23.55	15.00	89°56'41"	S44° 07' 06"E	21.20
C6	23.58	15.00	90°03'19"	N45° 52' 54"E	21.22
C7	23.55	15.00	89°56'41"	S44° 07' 06"E	21.20
C8	5.14	24.00	12°15'34"	N84° 46' 47"E	5.13
C9	5.82	24.00	13°53'41"	N82° 08' 36"W	5.81
C10	100.76	696.00	8°17'41"	N5° 51' 46"E	100.67
C11	11.51	696.00	0°56'52"	N1° 14' 30"E	11.51

LEGEND

- SECTIONAL MONUMENTATION (FOUND: TYPE, DATE, AGENCY AND LOCATION ETC. AS SHOWN ON THE PLAT).
- SPECIFIES SURVEY CONTROL MONUMENT TO BE SET (CLASS 1, RING & LID SET TO CITY STANDARD).
- SPECIFIES FRONT LOT PROPERTY CORNER OFFSET RIVET, OR NAIL & WASHER SET & OFFSET 6.0' IN CURB).
- SPECIFIES FRONT LOT PROPERTY CORNER OFFSET RIVET, OR NAIL & WASHER SET & OFFSET 1.0' IN CURB).
- SPECIFIES FRONT LOT PROPERTY CORNER OFFSET RIVET, OR NAIL & WASHER SET & OFFSET 9.5' IN CURB).
- ALL BOUNDARY AND PROPERTY (LOT) CORNERS TO BE SET WITH 5/8" REBAR AND CAP STAMPED B&G, UNLESS OTHERWISE SPECIFIED ON THE PLAT.

SURVEYOR'S CERTIFICATE

I, D. GREGG MEYERS, DO HEREBY CERTIFY THAT I AM A PROFESSIONAL LAND SURVEYOR, AND THAT I HOLD LICENSE NO. 312770 IN ACCORDANCE WITH TITLE 58, CHAPTER 22, PROFESSIONAL ENGINEERS AND LAND SURVEYORS LICENSING ACT AND HAVE COMPLETED A SURVEY OF THE PROPERTY DESCRIBED HEREON IN ACCORDANCE WITH SECTION 17-23-17 UTAH STATE CODE, AND HAVE VERIFIED ALL MEASUREMENTS AND PLACED MONUMENTS AS REPRESENTED ON THIS PLAT. I FURTHER CERTIFY THAT BY AUTHORITY OF THE HEREON OWNER(S), I HAVE SUBDIVIDED SAID TRACT OF LAND DESCRIBED HERE ON INTO LOTS, PUBLIC STREETS AND PUBLIC EASEMENTS, HEREAFTER TO BE KNOWN AS:

ANASAZI VISTA PHASE 1

BOUNDARY DESCRIPTION

BEGINNING AT A POINT THAT LIES NORTH 00°51'15" EAST 808.80 FEET, AND EAST 540.72 FEET, FROM THE WEST QUARTER CORNER OF SECTION 6, TOWNSHIP 42 SOUTH, RANGE 16 WEST, SALT LAKE BASE AND MERIDIAN, AND RUNNING THENCE NORTH 00°51'15" EAST 144.69 FEET; THENCE SOUTH 89°08'45" EAST 357.85 FEET; THENCE SOUTH 88°58'12" EAST 38.00 FEET; THENCE SOUTH 89°08'45" EAST 204.00 FEET; THENCE SOUTH 88°36'01" EAST 38.00 FEET; THENCE SOUTH 89°08'45" EAST 104.37 FEET TO A POINT ON THE WEST RIGHT-OF-WAY LINE OF KWAVASA DRIVE, THENCE ALONG SAID LINE THE FOLLOWING TWO (2) COURSES, 1) SOUTH 00°46'04" WEST 153.19 FEET AND 2) SOUTHERLY ALONG A 696.00 FOOT RADIUS CURVE TO THE RIGHT, (LONG CHORD BEARS SOUTH 05°23'20" WEST A DISTANCE OF 112.15 FEET), CENTER POINT LIES NORTH 89°13'56" WEST THROUGH A CENTRAL ANGLE OF 09°14'33", A DISTANCE OF 112.27 FEET; THENCE NORTH 89°05'26" WEST 600.00 FEET; THENCE NORTH 00°54'34" EAST 101.00 FEET; THENCE NORTH 89°05'26" WEST 107.73 FEET; THENCE WESTERLY ALONG A 100.00 FOOT RADIUS CURVE TO THE LEFT, (LONG CHORD BEARS SOUTH 87°22'50" WEST A DISTANCE OF 12.31 FEET), CENTER POINT LIES SOUTH 00°54'34" WEST THROUGH A CENTRAL ANGLE OF 07°03'28", A DISTANCE OF 12.32 FEET; THENCE NORTH 33°40'51" WEST 24.09 FEET, TO THE POINT OF BEGINNING.

CONTAINING 182,788 SQUARE FEET OR 4.20 ACRES.

07/06/2020
DATE:
BUSH AND GUDGELL INC.

PROFESSIONAL LAND SURVEYOR — LICENSE #312770 D. GREGG MEYERS — STATE OF UTAH

REVIEW
D. GREGG MEYERS
PROFESSIONAL LAND SURVEYOR UTAH
LICENSE NUMBER 312770

OWNER'S DEDICATION

KNOW ALL MEN BY THESE PRESENT THAT THE UNDERSIGNED OWNERS OF ALL THE ABOVE DESCRIBED TRACT OF LAND, HAVING CAUSED THE SAME TO BE SUBDIVIDED INTO LOTS, PUBLIC STREETS AND PUBLIC EASEMENTS, TO BE HEREAFTER KNOWN AS:

ANASAZI VISTA PHASE 1

FOR GOOD AND VALUABLE CONSIDERATION RECEIVED, DO HEREBY DEDICATE AND CONVEY TO IVINS CITY FOR PERPETUAL USE OF THE PUBLIC, ALL PARCELS OF LAND SHOWN ON THIS PLAT AS PUBLIC STREETS AND PUBLIC EASEMENTS. ALL PUBLIC STREETS, LOTS, AND PUBLIC EASEMENTS ARE AS NOTED OR SHOWN. THE OWNERS DO HEREBY WARRANT TO IVINS CITY AND ITS SUCCESSORS AND ASSIGNS TITLE TO ALL PROPERTY DEDICATED AND CONVEYED FOR PUBLIC USE HEREON AGAINST THE CLAIMS OF ALL PERSONS. LOTS SHOWN ON THIS PLAT ARE SUBJECT TO THE "DECLARATION OF COVENANTS, CONDITIONS AND RESTRICTIONS" APPLICABLE TO ENTRY NO. _____, DATED _____. SAID DECLARATION OF COVENANTS, CONDITIONS AND RESTRICTIONS ARE HEREBY INCORPORATED AND MADE PART OF THIS PLAT. REFERENCE IS MADE TO SAID DECLARATION FOR DETAILS CONCERNING THE RIGHT AND OBLIGATIONS OF PARTIES HAVING OR ACQUIRING AN INTEREST IN THIS DEVELOPMENT.

ANASAZI VISTA, LLC
(A UTAH LIMITED LIABILITY COMPANY)

BY: JAMES SULLIVAN

LIMITED LIABILITY ACKNOWLEDGMENT

STATE OF _____ } S.S.
COUNTY OF _____ }

ON THE ___ DAY OF _____, 20___, PERSONALLY APPEARED BEFORE ME, THE UNDERSIGNED NOTARY PUBLIC IN AND FOR SAID STATE AND COUNTY, JAMES SULLIVAN WHO BEING BY ME DULY SWORN, DID SAY THAT HE IS THE MANAGER/MEMBER OF ANASAZI VISTA, LLC, AND THAT HE EXECUTED THE FOREGOING OWNER'S DEDICATION ON BEHALF OF SAID LIMITED LIABILITY COMPANY BEING AUTHORIZED AND EMPOWERED TO DO SO BY THE OPERATING AGREEMENT OF ANASAZI VISTA, LLC, AND HE DID DULY ACKNOWLEDGE TO ME THAT SUCH LIMITED LIABILITY COMPANY EXECUTED THE SAME FOR THE USES AND PURPOSES STATED THEREIN.

_____
NOTARY PUBLIC
NOTARY PUBLIC FULL NAME: _____
COMMISSION NUMBER: _____
MY COMMISSION EXPIRES: _____
A NOTARY PUBLIC COMMISSIONED IN UTAH
STAMP IS NOT REQUIRED PER UTAH CODE 46-1-16(6)

ANASAZI VISTA PHASE 1

LOCATED IN
NORTHWEST 1/4 OF SECTION 6, TOWNSHIP 42 SOUTH, RANGE 16 WEST, SALT LAKE BASE AND MERIDIAN

PLANNING COMMISSION APPROVAL	CITY ENGINEER'S CERTIFICATE	APPROVAL AS TO FORM	APPROVAL AND ACCEPTANCE BY THE CITY OF IVINS	TREASURER APPROVAL	RECORDED NUMBER
ON THIS THE _____ DAY OF _____, A.D. 20____, THE PLANNING COMMISSION OF IVINS CITY, UTAH, HAVING REVIEWED THE ABOVE: "THE PALISADES AT SNOW CANYON PHASE 2, AMENDED AND EXTENDED" SUBDIVISION, AND HAVING FOUND THAT IT COMPLIES WITH THE REQUIREMENTS OF IVINS CITY, UTAH, PLANNING ORDINANCES, AND THE AUTHORIZATION GRATED BY THE IVINS CITY CODE HEREBY APPROVES SAID SUBDIVISION PLAT FOR RECORDING.	I, IVINS CITY ENGINEER, DO HEREBY CERTIFY THAT THIS OFFICE HAS EXAMINED THIS SUBDIVISION PLAT AND HAVE DETERMINED THAT IT IS CORRECT AND IN ACCORDANCE WITH INFORMATION ON FILE IN THIS OFFICE.	I, THE IVINS CITY ATTORNEY, DO HEREBY APPROVE THIS SUBDIVISION PLAT AS TO FORM, THIS ___ DAY OF _____, A.D. 20___.	THE IVINS CITY COUNCIL OF IVINS CITY, UTAH, GAVE PRELIMINARY PLAN APPROVAL FOR "THE PALISADES AT SNOW CANYON PHASE 2" SUBIDIVISON ON THE _____ DAY OF _____, A.D. _____.	I, WASHINGTON COUNTY TREASURER, CERTIFY ON THIS ___ DAY OF _____ A.D. 20__ THAT ALL TAXES, SPECIAL ASSESSMENTS, AND FEES DUE AND OWING ON THIS SUBDIVISION FINAL PLAT HAVE BEEN PAID IN FULL.	
ATTEST: CITY RECORDER, IVINS, UTAH — PLANNING COMMISSION CHAIRPERSON, IVINS, UTAH	CITY ENGINEER, IVINS, UTAH	CITY ATTORNEY, IVINS, UTAH	ATTEST: CITY RECORDER, IVINS, UTAH — MAYOR, IVINS, UTAH	WASHINGTON COUNTY TREASURER	WASHINGTON COUNTY RECORDER

No	Date	By	Revision

BUSH & GUDGELL, INC.
Engineers - Planners - Surveyors
205 East Tabernacle Suite #4
St. George, Utah 84770
Phone (435) 673-2337 / Fax (435) 673-3161
www.bushandgudgell.com

Drawn - BRS — Date - 07/06/2020
Designer - gmeyers@bushandgudgell.com
Checked - GM
Approved - GM
Scale - 1" = 50'
Job No - 201010

ANASAZI VISTA PHASE 1
LOCATED IN
NW 1/4 SECTION 6, T 42 S, R 16 W, SALT LAKE BASE & MERIDIAN

SHEET 1 OF SHEETS 1
FILE: 201010